



ND Deaf School  
.79 miles

Sweetwater School  
.31 miles

Ruger Park  
2.18 miles

Prairie View School  
.47 miles

# Devils Lake Bikepath Restoration

## 3.75 miles of Asphalt Path

STRAIGHTLINE INC.

WWW.STRAIGHTLINESEALIT.COM

7759 3RD ST S

MOORHEAD, MN 56560

# Estimate

Date	Estimate #
1/18/2016	1035

Name / Address
Kevin Fieldsend, Office Location - 919 5th St.SE Devils Lake, ND 58301 Phone: (701)662-7015 Fax: (701)662-7070

			Project
Description	Qty	Cost	Total
SEALCOATING 2 COATS OF SEALER TO 3.7 MILES OF BIKE PATH - 2 EVEN COATS OF SEALER - PITCH BLACK TRITAN SEAL SUPREME - WILL BE CLEANED PRIOR TO SEALING		32,100.00	32,100.00
CRACK SEALING BASED ON 28000 LN FT OF CRACKS THROUGH OUT THE 3.7 MILES OF PATH - CRACKS WILL BE BLOWN WITH NO LESS THEN 100 CFN 1/4 INCH NOZZEL AND FREE OF DEBREE - CRACKS WILL BE SEALED USING A MEADOWS 3405 HOT TAR SEALER - ALL CRACKS WILL BE SQUEEGEED		15,000.00	15,000.00
ESTIMATED TIME FOR START TO FINISH 2-3 DAYS EQUIPMENT USED AND WILL HAVE TO WITHSTAND IS 3/4 TON PICKUPS AND SMALL TRAILERS 10,900 POUNDS IF THERE IS RESTRICTIONS FOR THIS THE PRICE COULD CHANGE SLIGHTLY DEPENDING ON ACCESSIBILITY			
THANKS AGAIN STRAIGHTLINE INC.  701-799-8686 FAX 218-359-0806  WWW.STRAIGHTLINESEALIT.COM CALLSTRAIGHTLINE@YAHOO.COM		0.00	0.00
		<b>Total</b>	\$47,100.00

Customer Signature \_\_\_\_\_